BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT38316

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/16/2019-20, Date: 10.10.2019

Construction of Compound to Division office Building in ward no 08 Kodigehalli

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of N SIVAKUMARAA ( )		
				In Figures		In Words
1	468.43	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications	cum	460.67	215791.65	Rupees Four Hundred Sixty and Sixty Seven Paise Only
2	22.05	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180 Kgs using 40mm and down size graded granite metal, corse aggregates @ 0.85 cum and fine aggregtes @ 0.58cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cum	5234.65	115424.03	Rupees Five Thousand Two Hundred Thirty Four and Sixty Five Paise Only
3	51.77	Providing and constructing granite / trap / basalt size stone masonry in foundation cement mortar 1: 6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. - Available stones	cum	4715.49	244120.92	Rupees Four Thousand Seven Hundred Fifteen and Forty Nine Paise Only
4	15.52	Providing and constructing granite / trap / basalt size stone masonry in foundation cement mortar 1: 6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. - New stones	cum	5625.55	87308.54	Rupees Five Thousand Six Hundred Twenty Five and Fifty Five Paise Only
5	69.03	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.	sqm	145.69	10056.98	Rupees One Hundred Forty Five and Sixty Nine Paise Only
6	6.69	Providing and laying in position plain cement concrete of mix 1:2:4 with cement at 240 kg, with 20mm and down size graded granite metal coarse aggregate at 0.69 cum and fine aggregates at 0.459 cum, machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted for coping including cost of all materials, labour, HOM of machinery, curing, complete as per specifications with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.	cum	6202.17	41492.52	Rupees Six Thousand Two Hundred Two and Seventeen Paise Only
7	169.81	Providing and constructing load bearing wall with solid concrete blocks having block density not less than 1800kg/cum having a minimum average compressive strength of 4.00N/mm2 confirming to IS 2185(Part 1):2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials labour charges, scaffolding, curing , hire charges of machineries etc., complete as per specfications . KBS No.5.4 with solid concrete blocks of size 40x20x20cm	sqm	987.01	167604.17	Rupees Nine Hundred Eighty Seven and One Paise Only
8	396.9	Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications etc., complete with all leads and lifts as per the directions of the Enginee-in-charge of the work.	kg	97.47	38685.84	Rupees Ninety Seven and Forty Seven Paise Only
9	313.85	Providing 12mm thick cement plaster in single coat with cement mortar 1:6 to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work.	Sqm	198.01	62145.44	Rupees One Hundred Ninety Eight and One Paise Only

Signature of the contractor

20/02

Executive Engineer

10/02

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of N SIVAKUMARAA ( )		
				In Figures		In Words
10	313.85	Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications with all leads and lifts etc., complete as per the direction of Engineer-in-charge of the work. with primer	sqm	104.65	32844.40	Rupees One Hundred Four and Sixty Five Paise Only
11	148	Interlock tiles (PWDSR 2018-19, P.103, I. 14.7)	sqm	1138.86	168551.28	Rupees One Thousand One Hundred Thirty Eight and Eighty Six Paise Only
12	353.4	Chainlink fencing	Rm	418.6	147933.24	Rupees Four Hundred Eighteen and Sixty Paise Only
13	86.4	Rectangular poles fencing	Rm	881.33	76146.91	Rupees Eight Hundred Eighty One and Thirty Three Paise Only
14	194.37	Chainlink fencing	Sqm	733.59	142587.89	Rupees Seven Hundred Thirty Three and Fifty Nine Paise Only
15	255.6	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications.	sqm	360.5	92143.80	Rupees Three Hundred Sixty and Fifty Paise Only
16	28.75	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams.	cum	5482.1	157610.38	Rupees Five Thousand Four Hundred Eighty Two and Ten Paise Only
17	1.404	Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications	Tonne	71492.97	100376.13	Rupees Seventy One Thousand Four Hundred Ninety Two and Ninety Seven Paise Only
18	63.9	Providing and laying in position reinforced cement concrete M20 mix with stone aggregates 20mm and downsize for slab (including steel reinforcement) including centering and shuttering, maching mixed, concrete laid in layers not exceeding 15cm thick well compacted cost of all materials, labour, HOM of machineries, curing complete as per specifications.	Sqm	1995.0	127480.50	Rupees One Thousand Nine Hundred Ninety Five Only
19	398.17	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading with all leads and lifts as directed by the Engineer in charge of the work.	cum	83.18	33119.78	Rupees Eighty Three and Eighteen Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

10/02

10/02